





## Commercial

## INDUSTRY'S FASTEST INSTALLATION TIME + DRAMATIC COST REDUCTIONS

# CONVENTIONAL FOUNDATION INSTALLATION

2MW INSTALLATION

60+

**DAYS TO INSTALL** 



**OSPREY PowerRack™** 

2MW INSTALLATION

16

### **DAYS TO INSTALL**

- 4 person install teams
- Up to 12kW per hour
- Less mobilization to site

**\$145,000+** 

#### SAVINGS

- Savings due to field labor costs
- No pile driving
- No geotechnical report

# **SAVE TIME AND MONEY**



No Geotechnical Reports<sup>1</sup>



No Heavy Equipment



No Pounded Posts or Ground Screw



No Concrete or Ballast Blocks



Lowest Labor Cost in Solar Industry!

# The OSPREY PowerRack<sup>™</sup> is a patented ground mount solar racking system that has revolutionized the solar industry in terms of less mobilization, time to install and labor savings.

You hit a home run with this product!

— Jack Ramsey, CEO, AltSys Solar







### Saving Time and Money - 2MW commercial project

- Average installation time: < 60 minutes with 3-4 person crews</li>
- Lowest labor cost: < \$0.12/watt (includes: Racking, foundation, solar panels and anchor load testing)
- Save up to 416 man hours (52 days) per 2MW commercial project
- Save up to \$144,640 per 2MW

### **KEY SPECIFICATIONS**

- Solar panel manufacturer technology neutral with two designs: (OPR LTE, OPR MAX)
- Pre-engineered OSPREY's hold (12,16,20 or 24) solar panels in landscape orientation
- Total power output up to 12.96kW (24 x 540w solar modules)
- UL 2703 Compliant; Self-bonding mid clamps
- ASCE 7-16; Category 1
- Wind loads ≤ 130 mph and Snow loads ≤ 70+ psf.; (custom available)
- Fixed tilt orientation (15° to 35°); custom to 45°
- Engineered for N/S sloped terrain (< 10°); E/W sloped terrain (< 5°)</li>
- Pre-assembled independent power adjustable (front) legs 24" 51"
- Telescoping square tube (rear) legs to 101"
- Small footprint only (74" 82.5") spacing between front and rear legs
- ZAM275 or Galvanized (G90) steel finish standard; other options available
- 20-year limited product warranty protection
- MADE in USA (available)

### 100% Modular, Scalable and Universal Table Design

- Pre-engineered solar arrays; patented earth anchor foundation technology
- Install using handheld tools
- Interchangeable components used to assemble multiple table sizes: (4x3x2, 4x3x3, 4x4x2, 4x4x3, 4x5x3, 4x5x4, 4x6x4, 4x6x5)
- Stock and inventory efficiency
- Kitted and boxed hardware
- Less # SKUs
- Longest component 98"
- Stock on wooden pallets
- Deliver in van or box truck, overhead or back of pickup truck
- Safe and easy material handling

### **Sustainable Solution**

- Geotechnical report usually not required. Real-time soil verification and anchor load (pull) test achieved using proprietary OSPREY PowerJack™
- No concrete required
- Use up to 30 cubic feet of earth above each anchor installed. Soil and sediment act as natural ballast holding OSPREY PowerRack™ to ground
- Use of handheld tools reduce need for heavy equipment or machinery
- Less mobilization to site reduces project's carbon emissions (Co2)
- 100% removable; No long-term environment impact after life of solar system
- 100% transportable with Lift and Shift™ capability of renewable capital asset

### Structural Engineering

- Structural Calculation, Engineering Report with vertical and lateral analysis (dead load, live load, wind load, seismic load, etc.) provided all 50 US states
- Site-specific (wet stamp) structural engineering report (SSM) additional fee

MODEL	PANEL TYPE	FOOT PRINT	TILT	HEIGHT ADJ.	PANEL CONFIGURATIONS	WIND/SNOW
OPR LTE	(365w - 465w); 60c/72c	74"	15° - 35°	24" - 51"	4x3x2,4x3x3,4x4x2,4x6x4 4x4x3,4x5x3,4x5x4, 4x6x5	≤110; 30psf.
OPR-MAX <sup>1</sup>	(480w - 670w) <sup>2</sup> large format	82.5"	15° - 35°	24" - 51"	4x3x2,4x3x3,4x4x2,4x6x4 4x4x3,4x5x3,4x5x4, 4x6x5	≤110; 30psf.



<sup>&</sup>lt;sup>1</sup>Custom engineering available in Heavy Duty Snow Load < 70psf.; <sup>2</sup>Designed for large format panels < 45" Wide x 90"+ Long

<sup>\*</sup>Standard

<sup>\*\*110</sup>mph Standard